



FERN HOLLOW RESTORATION

SCHEMATIC DESIGN MEMORANDUM

MAY 2026

SUBMITTED BY:

ethos
collaborative
water-energy-climate-community

SUBMITTED TO:

 **upstream**
pittsburgh



Fern Hollow Creek, Image Credits: Upstream Pittsburgh

Project Team

Ethos Collaborative
6022 Broad Street, 2nd Floor
Pittsburgh, PA 15206



Upstream Pittsburgh
321 Pennwood Avenue, Suite 202
Pittsburgh, PA 15221



U.S. Army Corps of Engineers, Pittsburgh District
Planning and Environmental Branch
1000 Liberty Avenue
Pittsburgh, Pennsylvania 15222



Project Stakeholders

Pittsburgh Water
1200 Penn Avenue
Pittsburgh, PA 15222



City of Pittsburgh, Department of Public Works
414 Grant Street
Pittsburgh, PA 15219



Pittsburgh Parks Conservancy
West Tower, 317 E Carson St
Pittsburgh, PA 15219



Allegheny County Sanitary Authority
2200 Preble Avenue
Pittsburgh, PA 15233



Table of Contents

INTRODUCTION AND BACKGROUND4
 TIMELINE
EXISTING CONDITIONS.....6
 FERN HOLLOW STREAM AND VALLEY
 INFRASTRUCTURE CONDITIONS
DESIGN CONSIDERATIONS8
 SITE SELECTION & PROJECT SCOPE
 ENVIRONMENTAL CONSTRAINTS AND STANDARDS
EXISTING CONDITIONS PHOTO LOG.....10
GREEN INFRASTRUCTURE STRATEGIES + TYPOLOGIES.....12
 NETWORKED RIGHT-OF-WAY GREEN INFRASTRUCTURE: STREET CREEKS
 CURBED STORMWATER PLANTER
 RAIN GARDENS AND BIOSWALES
 POROUS GUTTER STRIP / PARKING LANE
 GREEN ALLEY
 SUBSURFACE STORAGE
BIDDLE PARKING LOT.....20
WETLAND.....22
CONFLUENCE24
CONFLUENCE ENLARGEMENT.....26
HENRIETTA GSI.....28
OVERTON GSI30
IMPLEMENTATION STRATEGY.....32

Introduction and Background


This memorandum builds on a decade of visioning, community engagement, and technical study in the Fern Hollow Creek corridor—including most recently the Fern Hollow Vision Plan, the USACE Water Resources Masterplan, and Upstream Pittsburgh's RIPPLE Watershed Plan—to advance the most constructable and actionable restoration framework developed for the valley to date. Where prior efforts established the foundation, this document provides the roadmap: a clear, site-specific path from planning to tangible project execution.

The central goal of this work is to restore sustainable flow and ecological function to Fern Hollow Creek. Decades of urbanization have severed the creek from the majority of its natural drainage area, leaving it intermittent through much of its length and vulnerable to the erosive forces of unmanaged stormwater. The five project areas described in this memorandum address this condition through a coordinated set of interventions: mitigating erosion and sedimentation that degrade the stream channel and its banks; improving and restoring natural stormwater flow pathways; rehabilitating riparian and wetland ecology; and increasing sustainable baseflow to the creek by reconnecting captured drainage through green stormwater infrastructure.

Rather than treating Fern Hollow as a single, monolithic restoration challenge, this document breaks the work into five discrete, right-sized projects—each independently implementable, each representing meaningful progress toward the larger restoration vision. For every project area, the document presents a schematic design, identifies the key barriers and constraints that must be resolved before construction, and outlines the next steps needed to move from this schematic framework to permitting, funding, and implementation. Taken together, these five projects constitute a credible, phased strategy for achieving lasting restoration of Fern Hollow Creek.



Timeline





PROJECT SITES

- 1 BIDDLE LOT GSI
- 2 WETLAND
- 3 CONFLUENCE
- 4 HENRIETTA STREET GSI
- 5 OVERTON STREET GSI

Master Plan Overview